NASA CR-171 837 C12-

# Impact of Lunar and Planetary Missions on the **Space Station**

LIBRARY COPY

Jan 19 1985

LANGLEY RESEARCH CENTER LIBRARY, NASA HAMPTON, VIRGINIA





CONTRACT NO. NAS9-17176

PRFLIMINARY REPORT SEPTEMBER 21, 1984 /:

**REPORT NO. 84-858** 

# **BEST**

# **AVAILABLE**

COPY

#### PRELIMINARY STS LOGISTICS REPORT

ON THE SPACE STATION

PREPARED FOR

PLANETARY EXPLORATION DIVISION ,

JOHNSON SPACE CENTER

BY EAGLE ENGINEERING

REPORT NUMBER 84-85B

CONTRACT NUMBER NAS9-17176

SEPTEMBER 21, 1984

#### · DRAFT 30 MINUTE PRESENTATION

- 1. TITLE
- 2. TASK DEFINTION
- 3. LUNAR OPERATIONS IMPACTS
- 4. LUNAR OPERATIONS IMPACTS
- 5. PLANETARY MISSIONS IMPACTS
- 6. IMPACT VERSUS NO IMPACT SPACE STATION
- 7. STUDY GROUNDRULES AND ASSUMPTIONS
- 8. STUDY GROUNDRULES AND ASSUMPTIONS
- 9. STUDY GROUNDRULES AND ASSUMPTIONS
- 10. LUNAR BASE DESCRIPTION
- 11. UNLOADING MODULE ON LUNAR SURFACE
- 12. LUNAR BASE BUILDUP SCHEME
- 13. LUNAR SCENARIO, EXPENDABLE LANDER
- 14. LUNAR SCENARIO, MANNED MISSION
- 15. COMMON MODULE AND TRAILER
- 16. LUNAR CRANE
- 17. VEHICLE DESCRIPTIONS
- 18. VEHICLE DESCRIPTIONS
- 19. AOTV STACK DEPARTING SPACE STATION WITH COMMON MODULE
- 20. AOTV
- 21. OTV SCHEDULED MAINTENANCE OPERATIONS

- 22. OTV SCHEDULED MANITENANCE OPERATIONS
- 23. OTV MANNED MODULE
- 24. E-LANDER, R-LEM, LARGE H2 TANK, AND LUNAR LANDER MANNED MODULE
- 25. LUNAR BASE LAUNCH REQUIREMENTS
- 26. DETAILED LAUNCH MANIFEST AND LUNAR MISSION SCHEDULE
- 27. DETAILED LAUNCH MANIFEST AND LUNAR MISSION SCHEDULE
- 28. DETAILED LAUNCH MANIFEST AND LUNAR MISSION SCHEDULE
- 29. DETAILED LAUNCH MANIFEST AND LUNAR MISSION SCHEDULE
- 30. COMMENTS AND CONCLUSIONS LUNAR BASE BUILD-UP AND OPERATIONS
- 31. MARS SAMPLE RETURN SCENARIO
- 32. MARS SAMPLE RETURN SPACE STATION CHECKOUT
- 33. CERES OR KOPFF SAMPLE RETURN SCENARIO
- 34. CERES OR KOPFF STACK
- 35. OMV RETURNS SAMPLE TO QUARANTINE MODULE
- 36. GLOVE BOX INSIDE QUARANTINE MODULE
- 37. MERCURY ORBITER SCENARIO
- 38. TITAN PROBES/SATURN ORBITER SCENARIO
- 39. PLANETARY MISSIONS PERFORMANCE SUMMARY
- 40. SHUTTLE LOADS REQUIRED FOR PLANETARY MISSIONS
- 41. COMMENTS AND CONCLUSIONS PLANETARY MISSIONS

IMPACT OF LUNAR AND PLANETARY MISSIONS
ON THE SPACE STATION

PREPARED FOR

PLANETARY EXPLORATION DIVISION,

JOHNSON SPACE CENTER

BY EAGLE ENGINEERING

#### TASK DEFINITION

#### LUNAR BASE MISSIONS

- O LUNAR BASE CONCEPTUAL DEFINITION
- O LUNAR ACTIVITIES LOGISTICS
- O DEFINE LUNAR SCENARIOS
- O SPACE STATION ELEMENTS REQUIRED
- O SPACE STATION FUNCTION
- O PRELIMINARY PROGRAM DEFINITION
- O UNCERTAINTIES IMPACT

#### PLANETARY MISSIONS

- O BASELINE EXPLORATION PLAN
  - O UNMANNED MISSION DEFINITION
  - O PLANETARY MISSION SCENARIOS
  - O SPACE STATION ELEMENTS REQUIRED
  - O SPACE STATION FUNCTION
  - O PHASED PLAN
    - O UNCERTAINTIES IMPACT

#### LUNAR OPERATIONS IMPACTS

O THE IMPACT OF THE LUNAR BASE ON THE SPACE STATION IS ONE OF SCALE - FLIGHT OPERATIONS MUST BE DONE MORE FREQUENTLY, WITH LARGER VEHICLES

PRIOR TO LUNAR OXYGEN PRODUCTION: EVERY TWO MONTHS FLIGHT OPERATIONS ARE:

- O' ONE UNMANNED LAUNCH VEHICLE (ULV) TANKER LAUNCH OF LOX/LH2 TO SS (100 M. TONS)
- O ONE SHUTTLE AFT CARGO CARRIER (ACC) LAUNCH WITH PAYLOADS, LUNAR LANDERS, CREWS, ETC
- O AT THE SPACE STATION TWO OTV'S, THE LANDER AND PAYLOAD(S) ARE CHECKED OUT & MATED INTO A STACK. THE OTV'S & LANDER ARE FUELED WITH LOX/LH<sub>2</sub>
- O THE LUNAR MISSION IS FLOWN AND THE OTV'S (PLUS MANNED MODULE ON MANNED SORTIES) RETURN TO SPACE STATION FOR DOCKING AND RECOVERY

AFTER LUNAR O2 PRODUCTION STARTS, FLIGHT OPERATIONS INCLUDE:

O TWO TANKER LAUNCHES

PLUS

O TWO STS LAUNCHES

FOR EVERY

O THREE LUNAR MISSIONS

#### LUNAR OPERATIONS IMPACTS

#### SPACE STATION HARDWARE


- O HANGERING AND STORAGE FOR 4 OPERATIONAL OTV'S
- O GANTRY'S FOR PREPARING TWO STACKS SIMULTANEOUSLY OF 2 OTV'S PLUS LUNAR LANDER, PLUS CARGOS (UP TO 3 ELEMENTS). STACKS WILL BE 30 TO 40 M (100 TO 135 FT) IN LENGTH & UP TO 15 M WIDE
- O PROPELLANT DEPOT WITH CAPACITY OF AT LEAST 2 TANKER LOAD UNITS OF 100 M TONS EACH
- O EQUIPMENT TO FUEL FROM DEPOT 2 OTVS PLUS LANDER WHILE MATED IN STACK FOR DEPARTURE. 98 M TONS LOX/LH2 TOTAL PER MISSION
- O ADDITIONAL HABITABILITY MODULE FOR HOUSING 2 TO 4 EXTRA SPACE STATION CREW AND TEMPORARY BILLETING FOR 4 TO 6 TRANSIENT LUNAR BASE PERSONNEL
- O 2 OMVS FOR FLIGHT SUPPORT
- SPACE STATION MANPOWER: EACH SIXTY DAYS THE SPACE STATION MUST PROVIDE FACILITIES AND MANPOWER FOR:
- O TRAFFIC CONTROL
  - RENDEZVOUS/DOCKING ACTIVITIES 1 TANKER, 1 SHUTTLE, 1 AFT CARGO CARRIER PAYLOAD, 2 OTV'S
  - 1 LUNAR DEPARTURE
  - 1 DEPOT ELEMENT REMOVAL FOR DEORBIT
- O VEHICLE CHECKOUT, MAINTENANCE AND REPAIR
  - 2 OTV SORTIES
  - 6 OMV SORTIES (4 DOCKING, 1 STACK DEPARTURE, 1 EMPTY DEPOT DEPARTURE FOR DEORBIT INITIATION)
  - 1 SET OF LUNAR VEHICLES & PAYLOADS (E-LANDER, OMM, E-LLMM/ASCENT, COMMON MODULE)
- O STACK ASSEMBLY AND FUELING SEQUENCE


## PLANETARY MISSIONS IMPACTS ON THE SPACE STATION

	Requirements	MARS SAMPLE RETURN	KOPFF SAMPLE RETURN	CERES SAMPLE RETURN	Mercury Orbiter	TITAN PROBES/ SATURN ORBITER
0	SPACE STATION HARDWARE REQUIRED					
	No. of OTVs Expended (NOT RETURNED)	Ø	1	1	Ø	1
	No. of OTV REFURB. KITS	1	2	2	1	1
	GANTRY TO STACK TWO STAGES		YES	YES		
	CHECKOUT EQUIP. FOR TWO STAGE STACK		YES	YES		
	QUARANTINE MODULE	YES	YES	YES		
	ADDITIONAL POWER, KW	5	5	. 5		
	ADDITIONAL THERMAL CONTROL, NO. OF STANDARD MODULES	1	1	1		
0	SPACE STATION MANHOURS REQUIRED					
	OTV REFURBISHMENT	52	1Ø3	1Ø3	52	52
	AEROBRAKE REMOVAL		21	21		21
	OTV/PayLoad Integration & C/O	11	21	21	11	11.
	FUEL, RELEASE, AND LAUNCH	24	36	36	24	24
	RENDEZ/RETRIEVE OTV USING OMV	12	12	12	12	
	SHUTTLE RENDEZ/PAYLOAD REMOVAL	2	2	11	2	2
	ULV PROPELLANT DELIVERY	7	17	18	7	1Ø
	SAMPLE RETRIEVAL USING OMV	8	8	8		
	SAMPLE ANALYSIS & SHIPMENT	24	16	16		
	TOTAL MISSION MANHOURS	138	235	246	1Ø5	118



No Impact





#### LUNAR & PLANETARY STUDY

#### GROUNDRULES & ASSUMPTIONS

- 1. THE SPACE STATION CAN STORE AND TRANSFER LOX AND LH2 TO THE ORBITAL TRANS-FER VEHICLE (OTV) IN ORBIT.
- 2. AEROBRAKING WILL BE A MATURE TECHNOLOGY AND IS INCORPORATED IN THE OTV DESIGN.
- 3. THE OTV WILL USE LOX/LH2 PROPELLANT.
- 4. ISP = 460 SEC WITH 1% START/STOP LOSSES YIELDING EFFECTIVE ISP = 455.4 SEC.
- 5. ALL STAGES, LUNAR LANDERS, ETC., WILL BE LOX/LH<sub>2</sub> UNLESS <u>STRONGLY</u> CONTRAINDICATED.

EXCEPTION - EXPENDABLE ASCENT STAGE WILL USE STORABLES.

- 6. Boil off rate for Cryogenic stages is 55 kg/day of LH2 per stage.
- 7. Cargo units for the Lunar base weigh a maximum of 18 metric tons.
- 8. The Lunar orbit Service Station wt = 35 M tons. It can store and transfer LH2 and LOX in orbit. On-orbit re-refrigeration capability for cryogenics is assumed.
- 9. OTV ELEMENTS CAN BE "STACKED" I.E. USED AS TWO IDENTICAL STAGES, ONE STAGING BEFORE THE OTHER IGNITES.
- 10. Lunar surface storage, transfer (into Landers), and re-refrigeration of cryogenics both LOX and LH2 is assumed after 02 production commences.

#### LUNAR & PLANETARY STUDY

# GROUNDRULES & ASSUMPTIONS (CONTINUED)

- 11. Major maintenance of the Lander is available either at the lunar base or at the lunar orbit service station.
- 12. For the purpose of this study: Lunar 02 will become available after delivery of the <u>production</u> plant to lunar surface. This 02 will be used in the reusable Lunar Lander, but delivery of Lunar 02 to Earth orbit will not be examined in this study.
- 13. The OTV WILL BE SIZED TO PERFORM ANY OF THREE REFERENCE MISSIONS:
  - A. Deliver 9 M tons to geosynchronous orbit, returning empty using a single stage.
  - B. Deliver 6 M tons round trip to geosynchronous orbit, using a single stage.
  - C. Deliver 18 M tons payload <u>Plus</u> a Lunar Lander (SIZED TO LAND THE PAYLOAD) TO LUNAR ORBIT, USING TWO OTV STAGES IN TANDEM. BOTH OTV STAGES ARE RETURNED TO THE SPACE STATION.
- 14. The same OTV's (with a kick stage where appropriate) can be used for the planetary mission. Alternate expendable stages (such as Centaur) can also be considered. Where feasible, OTV stages are recovered.
- 15. The Space Station altitude = 500 km (270 n mi).
- 16. LUNAR OPERATIONS WILL NOMINALLY HAVE A LAUNCH WINDOW EVERY NINE DAYS.

#### LUNAR & PLANETARY STUDY


# GROUNDRULES & ASSUMPTIONS (CONTINUED)

- 17. Lunar orbit operations will be at  $200\,$  km lunar altitude ( $109\,$  naut. Mi.).
- 18. LUNAR BASE WILL BE NEAR EQUATORIAL  $(\pm 4^{\circ})$ .
- 19. After stage 1 burnout of OTV, second stage coasts around (nearly) to perigee before ignition to minimize g-losses (2 burn option).
- 20. Propellant transfer to R-LEM takes place on Lunar Surface-H2 Tank is LANDED INTACT AND STORED ON THE SURFACE FOR REFRIGERATION AND PUMPING.
- 21. No Lunar Orbit Service Station is assumed.
- 22. LOX/LH2 MIXTURE RATIOS OF 7:1 ARE USED FOR ALL LUNAR LANDERS.
- 23. AFT CARGO CARRIER ON SHUTTLE EXTERNAL TANK IS ASSUMED AND USED.
- 24. Shuttle Derived-Unmanned Launch Vehicles (ULV) needed and assumed for propellant tankers. Launch 100 metric ton LOX/LH2 to Space Station per flight.
- 25. Launch Cost estimates (1984 dollars) ULV -\$133 Million/Launch STS -\$100 Million/Launch

#### LUNAR BASE DESCRIPTION

#### THE FINISHED LUNAR BASE CONSISTS OF:

- O 5 HABITABILITY MODULES
- O 5 RESEARCH UNITS
  - GEO-CHEMICAL LABORATORY
  - CHEMICAL/BIOLOGY LABORATORY
  - GEO-CHEMICAL/PETROLOGY LABORATORY
  - PARTICLE ACCELERATOR
  - RADIO TELESCOPE
- O 3 PRODUCTION PLANTS (PRECEEDED BY PILOT PLANTS)
  - OXYGEN PLANT
  - CERAMICS PLANT
  - METALLURGY PLANT
- 0 2 SHOPS
- 0 3 POWER UNITS
- O 1 EARTHMOVER/CRANE
- O 3 MOBILITY UNITS W/ TRAILERS
- 0 18 PERMANENT PERSONNEL
- ALL ASSEMBLED OVER A 10 YEAR BUILD-UP PERIOD




UNLOADING MODULE ON LUNAR SURFACE
PAINTING TO BE SUPPLIED

#### LUNAR BASE BUILD-UP SCHEME

- O FIRST 8 YEARS UNMANNED EXPLORATION & MAPPING
- O BASE BUILD-UP STARTS IN 2005
  - 1ST YEAR HABITAT POWER UNIT, CRANE, & 1 LABORATORY DELIVERED-UNMANNED 2 MANNED SORTIES FLOWN TO PREPARE BASE-ALL RETURN
  - 2ND YEAR MOBILITY UNIT & O2 PILOT PLANT DELIVERED-2 MORE MANNED SORTIES SMALL PERMANENT CREW STAYS
  - 3RD YEAR 1 MORE LAB & MISC. EQUIPMENT DELIVERED-UNMANNED - 3 MANNED SORTIES, ENTIRE CREW OF ONE MISSION STAYS SO THAT PERMANENT CREW HAS A LAUNCH VEHICLE ON SURFACE
  - 4TH YEAR OPERATIONAL OXYGEN PRODUCTION PLANT DELIVERED, REUSABLE LANDER/LAUNCHER (R-LEM) DELIVERED & BECOMES OPERATIONAL
  - 5TH YEAR HEAVY FLIGHT SCHEDULE TO DELIVER REMAINDER OF BASE ELEMENTS, THROUGH SLACKING OFF AS TO 6 MANNED CREW ROTATION SORTIES PER YEAR AS 10TH YEAR BASE APPROACHES FULL GROWTH MATURE BASE BY 10TH YEAR.


#### LUNAR SCENARIO, EXPENDABLE LANDER


- 1. Stack departs SS
- 2. First stage burn
- 3. Second stage burn
- 4. First stage returns to SS
- 5. Circularized in lunar orbit
- 6. Expendable lander places Common Module on lunar surface
- 7. Second stage returns to Earth
- 8. Aerobraking
- 9. Circularized above SS orbit
- 10. Second stage returns to SS




#### LUNAR SCENARIO, MANNED MISSION

- 1. Stack departs SS
- 2. Trans-lunar injection burn
- 3. First stage returns to SS
- 4. Second stage, lander, and manned module insert into lunar orbit
- 5. Lander descends
- 6. Ascent module departs lunar surface
- 7. Ascent module rendezvous with second stage
- 8. Second stage returns to earth with OMM, ascent module discarded
- 9. Aerobraking
- 10. Circularization above the SS orbit
- 11. Rendezvous with SS








#### LUNAR SPACE TRANSPORTATION SYSTEM

}	STS ELEMENTS	ELEMENT DESCRIPTION	ELEMENT FUNCTION AND DESIGN GOALS
	BASE ELEMENT COMMON MODULE	LENGTH = 11 M.; DIAMETER = 4.6 M. WEIGHT = 17.5 M. TON	COMMON LUNAR HOUSING AND/OR LABORATORY UNIT
]	E-LANDER	DIAMETER = 8.2 M.; HEIGHT = 7 M. WEIGHTS: BURN OUT = 3.8 M. TON USABLE PROPELLANT = 13.6 M. TON LOX/LH2 PROPELLANT	EXPENDABLE LUNAR LANDER DESIGNED TO DELIVER 17.5 M. TON TO LUNAR SURFACE
]	LUNAR LANDING MANNED MODULE (LLMM)	LENGTH = 3.6 M.; DIAMETER = 2.6 M WEIGHT = 3.25 M. TON (WITH 4 CREW)	MODULE TO CARRY CREW OF 4 TO LUNAR SURFACE, AND RETURN LIMITED LIFE SUPPORTNOT REUSED
]	E-LAUNCHER	DIAMETER = 3.6 TO 5 M. HEIGHT = 2 M. WEIGHTS: BURN OUT = 2.6 M. TON USABLE PROPELLANT = 5 M. TON PUMP FED, STORABLE PROPELLANT	EXPENDABLE LAUNCHER TO CARRY LLM PLUS .5 TON PAYLOAD FROM LUNAR SURFACE TO LUNAR ORBIT
]	OTV MANNED MODULE (OMM)	LENGTH = 2.6 M.; DIAMETER = 3 M. WEIGHT = 5.5 M. TON (WITH 4 CREW)	CREW MODULE FOR OTV, TO CARRY PERSONNEL FROM ORBIT TO ORBIT -SHIRT SLEEVE EVIRONMENTREUSABLE
	AEROBRAKING ORBITAL TRANSFER VEHICLE (AOTV)	DIAMETER = 12.2 M. (AERO SHIELD) LENGTH = 5 M. WEIGHTS: BURN OUT = 7.0 M. TON USABLE PROPELLANT = 42 M. TON LOX/LH2 PROPELLANT	OTV SIZED TO DELIVER 35 M. TON TO LUNAR ORBIT AND RETURN EMPTY USING TWO OTVS BOTH RETURNED BY AEROBRAKING REUSABLE

# LUNAR SPACE TRANSPORTATION SYSTEM

STS ELEMENTS	ELEMENT DESCRIPTION	ELEMENT FUNCTION AND DESIGN GOALS
REUSABLE LUNAR LANDER/LAUNCHER (R - LEM)	DIAMETER = 10 M.; HEIGHT = 7 M. WEIGHTS: BURN OUT = 5.2 M.TON USABLE PROPELLANT = 30 M.TON LOX/LH2 PROPELLANT	LUNAR BASED VEHICLE FOR TRANSPOR FROM LUNAR SURFACE TO LUNAR ORBIT AND BACK - USING LUNAR PRODUCED OXYGEN. DESIGNED FOR 17.5 TON PL DOWN, Ø UP OR 14 TON PL DOWN, 7 TON UP A 5 TON TANK OF LH2 IS ALSO CARRIED DOWN ON EACH LANDING
REUSABLE LUNAR LANDING MANNED MODULE (R - LLMM)	LENGTH = 5 M.; DIAMETER = 2.6 M. WEIGHT = 5 M. TON (WITH 6 CREW)	LUNAR BASED MANNED MODULE FOR US WITH R-LEM; NORMAL CREW 6, MAX 1
LARGE OMM	LENGTH = 4 M.; DIAMETER = 3 M. WEIGHT = 8 M. TON (WITH 6 CREW)	LARGER OMM REPLACEMENT; FOR ORBITAL TRANSPORT OF CREWS IN MATURE LUNAR BASE OPERATIONS NORMAL CREW 6, MAX. 10
H2 TRANSFER TANK	VOLUME = 57 CU.M. WEIGHTS: EMPTY WT.=1 M.TON FULL WT.= 5 M.TON	TANK OF LIQUID HYDROGEN FUEL FOF R-LEM (WITH LUNAR O2) - ONE DELIVERED TO LUNAR SURFACE STORAGE EACH FLIGHT
	LAUNCH VEHICLES	
SHUTTLE (STS)	PL TO SPACE STATION = 25 M. TON	REUSABLE LAUNCH VEHICLE FOR VALUABLE CARGOS AND PERSONNEL
SHUTTLE/AFT CARGO CARRIER (STS-ACC)	PL TO SPACE STATION = 22 M. TON	SHUTTLE WITH A CARGO COMPARTMENT ON AFT END OF EXTERNAL TANK -FOR OVERSIZE CARGOS-
SHUTTLE DERIVED UNMANNED LAUNCH VEHICLE (SD-ULV)	USABLE LOX/LH2 TO SPACE STATION = 100 M.TON	UNMANNED LAUNCHER DESIGNED USING SHUTTLE ELEMENTS, USED FOR LAUNCHING LOX/LH2 PROPELLANT TO ORBITAL STORAGE DEPOT



AOTV STACK DEPARTING SPACE STATION
WITH COMMON MODULE
PAINTING TO BE SUPPLIED

AOTV

PAINTING TO BE SUPPLIED

# OTV SCHEDULED MAINTENANCE OPERATIONS

DURATION 1 DAY	REMOVE AND REPLACE FUEL CELL/BATTERY 2 PEOPLE	5:40	MANHOURS
DURATION 2 DAYS	REMOVE AND REPLACE ENGINE 4 PEOPLE	65:3Ø	MANHOURS
	OTV UNSCHEDULED MAINTENANCE OPERATIONS		
DURATION 1 DAY	REMOVE AND REPLACE AVIONICS MODULE 2 PEOPLE	5:30	MANHOURS
DURATION 1 DAY	REPAIR AEROBRAKE 4 PEOPLE	26:20	MANHOURS
DURATION 2 DAYS	REMOVE AND REPLACE TANK MODULE 4 PEOPLE	58:15	MANHOURS

#### OTV TURNAROUND OPERATIONS


#### 110 INUKIMAL U11 2 PF

DURATION 4 DAYS

NORMAL OTV TURNAROUND 2 PEOPLE


69:40 MANHOURS

- O RETRIEVAL AND CAPTURE
- O SAFING
- O BERTHING
- O INSPECTION
- O REMOVE AND REPLACE ACS MODULES
- O SYSTEMS TEST
- O PAYLOAD INTEGRATION
- O TRANSFER PROPELLANT
- O PRELAUNCH
- O LAUNCH




OMM
OTV MANNED MODULE
DETAILED SKETCH TO BE SUPPLIED

# EXPENDABLE LANDER - DRAFT SKETCH



# LUNAR BASE LAUNCH REQUIREMENTS



MONTH	LAUNCH NO.	TYPE	CARGO MANIFEST	CARGO WT. M. TON	LUNAR FLIGHT NO.	FL IGHT TYPE
			YEAR 2005			
JAN	5-1	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		
FEB	5-2	STS-ACC	E-LANDER,+BASE ELEMENT #1	21	L5-1	UNMANNED
MARCH	5-3	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		DEL IVERY
APR IL	5-4	STS-ACC	E-LANDER,+BASE ELEMENT #2	21	L5-2	UNMANNED
MAY	5-5	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		DEL IVERY
JUNE	5-6	STS-ACC	E-LANDER,+BASE ELEMENT #3	21	L5-3	UNMANNED
JULY	5-7	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		DEL IVERY
AUG	5-8	STS-ACC	E-LANDER,+BASE ELEMENT #4	21	L5-4	UNMANNED
SEPT	5-9	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		DEL IVERY
OCT	5-10	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +OMM, +4 CREW	20	L5-5	MANNED
NOV	5-11	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		SORTIE
DEC	5-12	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +OMM, +4 CREW	2Ø	L5-6	MANNED

•

MONTH	LAUNCH NO.	TYPE	CARGO MANIFEST	CARGO WT. M. TON	LUNAR FL IGHT NO.	FL IGHT TYPE
			YEAR 2006			
JAN	6-1	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		
FEB	6-2	STS-ACC	E-LANDER,+BASE ELEMENT #5	21	L6-1	UNMANNED DEL IVERY
MARCH					·	DLLIVLKI
APR IL	6-3	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		
MAY	6-4	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +4 CREW, +2 TON P.L., + 4 TON OF AOTV ELEMENTS	2Ø	L6-2	MANNED SORTIE
JUNE			1, E, 77 4 TON OF ACTV LELIENTS			SUNTIL
JULY	6-5	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		
AUG	6-6	STS-ACC	E-LANDER, +BASE ELEMENT #6	21	L6-3	UNMANNED DEL IVERY
SEPT						DLLIVERI
OCT	6-7	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		
NOV	6-8	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +4 CREW, +2 TON P.L., + 4 TON OF AOTV ELEMENTS	2Ø	L6-4	MANNED SORT IE
DEC			F.L., T 4 IUN UF AUTV LLLILINIS			SUNTIL

MONTH_	LAUNCH NO.	TYPE	CARGO MANIFEST	CARGO WT. M. TON	LUNAR FL IGHT NO.	FL IGHT TYPE
			YEAR 2007			
JAN	7-1	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		
FEB	7-2	STS-ACC	E-LANDER,+BASE ELEMENT #7	21	L7-1	UNMANNED DEL IVERY
MARCH						DELIVERI
APR IL	7-3	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		
MAY	7-4	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +4 CREW, +2 TON	2Ø	L7-2	MANNED -
JUNE			P.L.,+ 4 TON OF AOTV ELEMENTS			SORTIE
JULY	7-5	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		
AUG	7-6	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +4 CREW, +2 TON	2Ø	L7-3	MANNED
SEPT			P.L.,+ 4 TON OF AOTY ELEMENTS			SORTIE
OCT	7-7	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	1ØØ		•
NOV	7-8	STS-ACC	E-LANDER, +E-LLMM/ASCENT, +4 CREW, +2 TON	21	L7-4	MANNED
DEC	7-9 7-10	STS-ACC SD-ULV	P.L.,+ R-LLMM R-LEM ELEMENTS,+SECOND R-LLMM,+H2 TANK LOX/LH2 PROPELLANT SUPPLY UNIT	1Ø 1ØØ		SORTIE


Month 	LAUNCH NO.	TYPE	CARGO MANIFEST	CARGO WT. M. TON	LUNAR FL IGHT NO.	FL IGHT TYPE
			YEAR 2008			
JAN	8-1	STS-ACC	E-LANDER,+BASE ELEMENT #8	21	L8-1	UNMANNED
FEB	8-2	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		DEL IVERY
MARCH	8-3	STS-ACC	E-LANDER,+BASE ELEMENT #9	21	L8-2	UNMANNED
APR IL MAY	8-4 NOTE	SD-ULV LUNAR CREW	LOX/LH2 PROPELLANT SUPPLY UNIT DELIVERED TO SPACE STATION ON SCHEDULED	100 RESUPPLY S	TS LAUNCH L8-3	MANNED
JUNE	8-5	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100		SORTIE
JÜLY	8-6	STS	2 H2 TANKS,+ 18 TONS OF LUNAR CARGO, + 4 CREW	21	L8-4	MANNED
AUG	8-7	SD-ULV	LOX/LH2 PROPELLANT SUPPLY UNIT	100	TC I ALBIGIA	SORTIE
SEPT	NOTE	- LUNAR CREW	DELIVERED TO SPACE STATION ON SCHEDULED	RESUPPLY S	L8-5	MANNED
OCT	8-8	STS	2 H2 TANKS, + 18 TONS OF LUNAR CARGO,	21		SORTIE
NOV DEC			+ 4 CREW		L8-6	MANNED SORT IE


# COMMENTS AND CONCLUSIONS LUNAR BASE BUILD-UP AND OPERATIONS

- O THE LUNAR INITIATIVE REQUIRES HEAVY UTILIZATION OF THE SPACE STATION AS AN OPERATIONS CENTER AND TRANSPORTATION DEPOT
- O STORAGE, MAINTENANCE, AND OPERATIONS OF PERMANENT AND TRANSIENT TRANSPORTATION SYSTEM ELEMENTS REQUIRE EXTENSIVE HANGERS, GANTRYS, AND SHOP AREAS, PLUS 2 TO 4 ADDITIONAL SPACE STATION CREW MEMBERS
- O ADDITIONAL PERSONNEL MODULE(S) WILL BE NECESSARY FOR ENLARGED SS CREW PLUS 4 TO 6 TRANSIENTS (25% OF TIME)
- O LARGE OTV'S WITH MULTI-STAGING CAPABILITY ARE REQUIRED
- O ULV TANKER LAUNCHES ARE REQUIRED TO ACHIEVE REASONABLE LAUNCH RATES PROVIDES LAUNCH COST SAVINGS OF \$1.5 BILLION/YEAR COMPARED TO NSTS ALONE.
- O LUNAR TRANSPORTATION OPERATIONS ARE FAIRLY INTENSE BUT ENTIRELY PRACTICABLE. REQUIRES ONE LAUNCH PER MONTH, ONE LUNAR FLIGHT EVERY 2 MONTHS

### MARS SAMPLE RETURN SCENARIO


- 1. Stack Leaves S.S.
- 2. Trans-Mars Injection
- 3. Trans-Mars Voyage
- 4. Aerocapture/Mars Orbit Insertion
- 5. Jettison Orbiter Aeroshell
- 6. Lander and Orbiter Separate
- 7. Lander Enters Mars Atmosphere
- 8. Landing on Mars
- 9. Collect Samples
- 10. Launch from Mars
- 11. Rendezvous Maneuvers
- 12. Rendezvous with Orbiter
- 13. Trans-Earth Injection
- 14. Trans-Earth Voyage
- 15. Earth Orbit Insertion
- 16. Rendezvous with OMV
- 17. Return to S.S.





MARS SAMPLE RETURN
SPACE STATION CHECKOUT
PAINTING TO BE SUPPLIED


- 1. 2 OTVs, MMII, 2 Samplers, and EOC leave SS
- 2. First stage separates and returns to SS
- 3. Second stage and spacecraft enroute to comet/asteroid
- Spacecraft surveying asteroid/comet
- 5. Landers on surface, Spacecraft orbiting
- 6. Spacecraft recovers samples and departs for Earth
- 7. MMII and EOC enroute to Earth
- 8. MMII and EOC separate
- 9. EOC aerobrakes
- 10. EOC circularization burn, 470 nm x 470 nm final orbit
- 11. OMV retrieves EOC to Quarantine Module





# CERES STACK

DETAILED SKETCH TO BE SUPPLIED



OMV RETURNS SAMPLE TO QUARANTINE MODULE

PAINTING TO BE SUPPLIED

GLOVE BOX INSIDE QUARANTINE MODULE

SKETCH TO BE SUPPLIED

MERCURY ORBITER SCENARIO

SKETCH TO BE SUPPLIED


TITAN PROBES/SATURN ORBITER SCENARIO
SKETCH TO BE SUPPLIED


#### PLANETARY MISSIONS PERFORMANCE SUMMARY

	C3	TYPE OF OTV*	PAYLOAD OUT OF LEO	LEO TOTAL DEPARTURE MASS	OTV PROPELLANT LOAD	PROPELLANT + PAYLOAD (LIFT REQ.)
	(KM/SEC)^	2	METRIC TONS	METRIC TONS	METRIC TONS	METRIC TONS
MARS SAMPLE RETURN	9.0	1 Stage Reusable	8.89	43.53	27.41	36.31
KOPFF SAMPLE RETURN	8Ø.7	2 STAGE, 1st Stage Returns	8.38	91.76	71.Ø8	79.46
CERES SAMPLE RETURN	9.9	2 STAGE, 1st STAGE RETURNS	43.57	131.24	75.42	118.99
MERCURY ORBITER	18.7	1 STAGE REUSABLE	5.63	41.Ø2	28.46	34.Ø8
TITAN PROBES/ SATURN ORBITER	5 <b>0.</b> 5	1 STAGE EXPENDABLE	6.34	52.90	41.30	47.65

<sup>\*</sup> ISP = 455.4 SEC., ALL STAGES HAVE A TOTAL PROPELLANT CAPACITY OF 40 METRIC TONS, A = 3.731 KGMS, B = .0785. STAGES THAT DO NOT RETURN HAVE THE AEROBRAKE REMOVED.

# SHUTTLE LOADS REQUIRED





# COMMENTS AND CONCLUSIONS PLANETARY MISSIONS

- O THE IMPACT OF THE PLANETARY MISSIONS STUDIED ON THE SPACE STATION IS NOT LARGE WHEN COMPARED TO THE LUNAR BASE
- O A QUARANTINE MODULE MAY BE DESTRABLE FOR SAMPLE RETURNS
- O THE KOPFF AND CERES MISSIONS REQUIRE THE CAPABILITY TO STACK AND CHECKOUT TWO STAGE OTVS
- O 2 TO 7 MANWEEKS OF ON-ORBIT WORK, DEPENDING ON THE MISSION COMPLEXITY, WILL BE REQUIRED OF THE CREW OF THE STATION TO LAUNCH A MISSION
- O WITH THE POSSIBLE EXCEPTION OF QUARANTINE MODULE WORK, DEDICATED CREW WILL NOT BE REQUIRED

**End of Document**